Abstract of estimate for constructing a building for locating the Urdu Middle School for Mysore State Troops at Hebbel, Bangalore.

Serial No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
1	Earthwork excavation	C.yd.	96		
2	Metal concrete for foundation	C.ft.	859		
3	Stone in clay	„	1937		
4	Burnt brick in clay	„	3458		
5	Burnt brick in mortar	„	163		
6	Burnt stone slabs 6" dressed and fixed ...	S.ft.	767		
7	Burnt stone pillars with 2 line dressing allround	„	88		
8	Arch work—burnt brick in mortar ..	C.ft	82		
9	Teakwood doors with panelled shutters, bolts, hinges, etc., complete.	S.ft.	140		
10	Teakwood windows with panelled shutters, and iron bars with fittings complete.	„	173		
11	Teakwood ventilators with glazed shutters and iron bars, etc., complete.	„	36		
12	Teakwood circular ventilators, with glazed shutters, etc., complete.	„	28		
13	Teakwood work wrought and put up with wood-oiling.	Sqr.	208·63		
14	Roofing with I class Mangalore tiles on teak reepers.	„	30·47		
15	Plastering with chunam mortar ...	„	70·91		
16	White washing	„	70·91		
17	Flooring with Cuddappah slabs on 3" concrete bed with cement pointing.	„	17·75		
18	Cement pointing to basement	„	3·66		
19	Chacholate painting	„	6·90		
20	Teakwood eave board with painting ...	R.ft.	262		
21	Teakwood finials	Each	6		
22	Teakwood pendants	„	10		
23	Mangalore ridge tiles set in mortar ...	R.ft.	111		
24	Valley with zinc sheets and teak planks including chunam borders and cement pointing 1½' on each side.	„	57		
25	Cornice work for front gables	„	74		
26	Cutting grooves in pillars	Each	8		
27	Chunam borders	R.ft.	120		
28	Earthwork filling in basement	C.yd.	92		
29	Levelling ground and clearing site ...	Lump	sum		

N. NARASIMHA IYENGAR,
Assistant Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification, dated 20th February 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 6th March 1933, for constructing a Tank near Hirekolale in Head Works of Chikmagalur Water Works. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M., on all Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash as earnest money, and be superscribed "Tender for constructing a Tank near Hirekolale in Head Works of Chikmagalur Water Works" in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities for constructing a Tank near Hirekolale in Head Works of Chikmagalur Water Supply.

No.	Items of work	Unit	Quantity
	Bund.		
1	Removing silt	C.yds.	459
2	Earthwork for bund watering and tamping ...	,,	1517
3	Re-using earth, watering and tamping	,,	230
4	New stone revetment with jelly packing	,,	265½
5	Putting masonry wall at channel place	As per actual measurements.	
6	Turfing the slopes of bund with watering	S.yds.	854
7	Gravel admixture using for bund with watering and tamping.	C.yds.	400
8	Jungle clearing	Lump sum	
	Weir.		
1	Earthwork excavation	C.yds.	112
2	Concrete in surki mortar	,,	413
3	Burnt brick in surki mortar	C.ft.	962
4	Surki mortar plastering	Sqr.	9·00
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	262
6	Rough stone work including jelly packing	C.yds.	100
7	Providing grade stones as per standard design ...	No.	5
8	Do B. M. stones do	,,	2
9	Do Register No. stone do	,,	1

B. R. GARUDACHAR,
Executive Sanitary Engineer.

IN THE COURT OF THE ASSISTANT REGISTRAR OF CO-OPERATIVE SOCIETIES, MYSORE DIVISION, MYSORE.

Suit was filed against Mr. M. Rangappa, in the above Court and for want of correct whereabouts, the summons could not be served on him. The final date of Hearing is posted to 1*st March* 1933. If the defendant does not appear on the Hearing Date at 11 o'clock, before the Court of the Assistant Registrar, he will be treated as *Ex-parte*.

Case No. 672 of 31-32. Suit for Rs. 275-0-6 with interest from 22nd May 1932.

Plaintiff. — *Defendant.*

The Mysore Co-operative Society, Ltd., Mysore. *vs.* M. Rangappa, Contractor, Hospital Road, Mysore.

S. SUBBA RAO,
Honorary Secretary.